




Present Status and Future Plans for Linear Accelerators in Korea


2026. 08. 17.

Yeonsei Chung

Institute for Rare Isotope Science, IBS, KOREA

Major Accelerator Facilities in Korea







Contents


1. KOMAC Status and Plan
2. PAL-XFEL Status and Plan
3. KLS Status and Plan
4. RAON Status and Plan
5. Summary and Outlook

KOMAC at Gyeongju




KOMAC (Korea Multipurpose Accelerator Complex)

- Gyeongju branch of Korea Atomic Energy Research Institute (KAERI)
- 100 MeV Linac in Operation since 2013




KOMAC 100 MeV LINAC and Beamlines Status


- Linac commissioned in 2013
- General purpose beamline and user service starts (2013~)
- RI production beamline (2016~)
- Low flux beamline (2017~)
- * Accelerator test beamline (2017~)
- * Prototype RI beam production beamline (2018~)
- * Pilot operation of neutron beam test (2018~)
- Official operation of neutron beam service (2024 ~)
- Total 4 proton beamlines and 1 neutron beamline are in user service as of 2025
(TR23, TR101, TR102, TR103, Tunnel)



Linac statistics




User statistics




Recent Activities

Machine Aging Control (Spare RFQ and DTL) : Spare RFQ under fabrication, Replacing EMQ with PMQ in DTL, New DTL tank



Spare RFQ development




DTL with PMQ development




Beam Test Stand (BTS) : Ion source and LEBT study, LLRF control algorithm development, Beam diagnostics study





BTS (1 MeV RFQ)



LLRF control algorithm




Beam diagnostics study





Machine learning


RI Beam Production and Neutron Beam Service



Target ion source and Li-8 beam production




Neutron production for user service




Upgrade and Future Plan

Operational Status of the KOMAC 100 MeV Proton Linac and Pilot R&D for the 200 MeV Upgrade (TU1A001) By Dr. Han-Sung Kim




Short-term Plan : 200 MeV Energy Upgrade



- Beam species: Proton
- Maximum energy: 200 MeV
- Beam size: 100 mm X 100 mm
- Uniformity: < 10%
- Flux range: $10^6 \sim 10^8$ p/cm² s




- Beam species: Neutron, proton
- Neutron maximum energy: 200 MeV
- Neutron flux: $> 10^8$ n/cm² s (> 10 MeV)
- Proton maximum energy: 200 MeV






Long-term Plan : Spallation neutron source with Proton RCS

- 1 GeV RCS (2 GeV upgradable)
- Neutron target
- Instruments and Beam utilization facility




PAL-XFEL at Pohang



PAL-XFEL overview




Main parameters

e ⁻ Energy	4-10.5 GeV (Hard X-ray line), 3 GeV (Soft X-ray line)
e ⁻ Bunch charge	250 pC
Slice emittance	0.3 mm mrad
Repetition rate	60 Hz
Pulse duration	20 fs – 30 fs
Peak current	~3 kA
Operation mode	SASE, Self-seeding, Two-color, and etc.




PAL-XFEL project timeline
Apr. 2011: PAL-XFEL project started
Jun. 2012: Ground-breaking
Dec. 2014: Building completed
Jan. 2016: Installation completed
Apr. 2016: Commissioning started
Jun. 2017: User service started

User Beamtime
: 190 Days
(24-hour Operation)



Sub - 20 femtosecond timing stability




- ❖ **S-band 4 hole photocathode gun, quasi-coupler acc. and SLED structures 0.01 deg temperature control.**
- ❖ **20 ppm CCPS type modulator**
- ❖ **Sub femtosecond jitter in reference timing distribution over 1 km distance**

ARTICLES
nature
photonics



Hard X-ray free-electron laser with femtosecond-scale timing jitter

Heung-Sik Kang^{1*}, Chang-Ki Min^{1,4}, Hoon Heo¹, Changbum Kim¹, Haeryong Yang¹, Gyu Jin Kim¹, Inhyuk Nam¹, Soung Youl Baek¹, Hyo-Jin Choi¹, Geonyeong Mun¹, Byoung Ryul Park¹, Young Jin Suh¹, Dong Cheol Shin¹, Jinyul Hu¹, Juho Hong¹, Seonghoon Jung¹, Sang-Hee Kim¹, KwangHoon Kim¹, Donghyun Na¹, Soung Soo Park¹, Yong Jung Park¹, Jang-Hui Han¹, Young Gyu Jung¹, Seong Hun Jeong¹, Hong Gi Lee¹, Sangbong Lee¹, Sojeong Lee¹, Woul-Woo Lee¹, Bonggi Oh¹, Hyung Suck Suh¹, Yong Woon Park¹, Sung-Ju Park¹, Min Ho Kim¹, Nam-Suk Jung¹, Young-Chan Kim¹, Mong-Soo Lee¹, Bong-Ho Lee¹, Chi-Won Sung¹, Ik-Su Mok¹, Jung-Moo Yang¹, Chae-Soon Lee¹, Hocheol Shin¹, Ji Hwa Kim¹, Yongsam Kim¹, Jae Hyuk Lee¹, Sang-Youn Park¹, Jangwoo Kim¹, Jaeku Park¹, Intae Eom¹, Seungyu Rah¹, Sunam Kim¹, Ki Hyun Nam¹, Jaehyun Park¹, Jaehun Park¹, Sangsoo Kim¹, Soonam Kwon¹, Sang Han Park¹, Kyung Sook Kim¹, Hyojung Hyun¹, Seung Nam Kim¹, Seonghan Kim¹, Sun-min Hwang¹, Myong Jin Kim¹, Chae-yong Lim¹, Chung-Jong Yu¹, Bong-Soo Kim¹, Tai-Hee Kang¹, Kwang-Woo Kim¹, Seung-Hwan Kim¹, Hee-Seock Lee¹, Heung-Soo Lee¹, Ki-Hyeon Park¹, Tae-Young Koo¹, Dong-Eon Kim¹ and In Soo Ko²



High brightness self-seeding based on energy (phase space) stability


Electron energy jitter: 0.012% rms
Photon energy jitter: 0.025% rms



nature
photonics

High-brightness self-seeded X-ray free-electron laser covering the 3.5 keV to 14.6 keV range


Inhyuk Nam^{1,4}, Chang-Ki Min^{1,4}, Bonggi Oh^{1,4}, Gyu Jin Kim¹, Donghyun Na¹, Young Jin Suh¹, Haeryong Yang¹, Myung Hoon Cho¹, Changbum Kim¹, Min-Jae Kim¹, Chi Hyun Shim¹, Jun Ho Ko¹, Hoon Heo¹, Jaehyun Park¹, Jangwoo Kim¹, Sehan Park¹, Gisu Park¹, Seonghan Kim¹, Sae Hwan Chun¹, Hyojung Hyun¹, Jae Hyuk Lee¹, Kyung Sook Kim¹, Intae Eom¹, Seungyu Rah¹, Deming Shu², Kwang-Je Kim², Sergey Terentyev³, Vladimir Blank³, Yuri Shvyd'ko^{2,4}, Sang Jae Lee^{1,4} and Heung-Sik Kang^{1,4}



Ongoing Upgrade Project

2nd FEL line of PAL-XFEL (HX2) to meet the increasing demand for user beamtime



- ❖ Funding for the 2nd FEL Line of PAL-XFEL (HX2) starting in 2026
- ❖ Photon energy bandwidth: 1.5 ~ 10 keV
 - Over 3mJ FEL Pulse Energy from 1.5 to 8 keV (Over double HX1)
 - Best performance in stability (Timing jitter, Pointing jitter)
 - 20 undulators and self-seeding
- ❖ Simultaneous operation of 2 FEL lines
- ❖ Construction of 2 Experimental Stations



Resonant kicker for the simultaneous HX/SX operation

- ❖ Two bunches spaced by ~25 ns from the gun are split into the HX and SX lines; both beamlines provide FEL at 60 Hz.
- ❖ A resonant kicker system (~50 MHz, on-crest operation with a 180-degree phase difference), similar to that of SwissFEL, is under design.
- ❖ Preliminary tests for the laser system have been completed.
- ❖ A BPM electronics simulator for two electric pulses has been implemented. Various filters are currently being tested.

KLS at Ochang



KLS Construction Project Overview



Project Period	July 2021 – December 2029 (8.5 years)	Facility Scale	Site Area: 540,000 m² ※ Including base site of 310,000 m ² Total Floor Area: 69,525 m²
Lead Organizations	Ministry of Science and ICT / Chungcheongbuk-do / Cheongju City ※ (Government) Equipment & research facility construction, etc. (Local governments) Land, ancillary facilities, etc.		
Project Cost	Total: KRW 1,164.3 Billion (National) KRW 964.3B / (Local) KRW 200.0B (land acquisition, etc.) Total cost ▲ Managed scope: KRW 1,053.5B ▲ Outside managed scope: KRW 110.8B		
Location	Ochang-eup, Cheongju-si, Chungcheongbuk-do (within Ochang Techno-Polis Industrial Complex)		
Design Specifications	Electron Beam Energy: 4 GeV (Storage ring circumference: approx. 800 m) Beam Emittance: ≤ 100 pm·rad (Design target: 58 pm·rad) Beamlines: 40+ (Insertion device beamlines: 24) Acceleration method: Electron gun → Injector LINAC → 4 GeV Booster Lattice: MBA-based 7BA electron optics array		

KLS Beamlines

Priority support for Industries

- ① BioPharma-BioSAXS ② Material Structure Analysis
- ③ Soft X-ray NanoProbe

Support for Academic R&D

- ④ Nanoscale Angle-resolved Photoemission Spectroscopy
- ⑤ Coherent X-ray Diffraction
- ⑥ Coherent Small-angle X-ray Scattering
- ⑦ Real-time X-ray Absorption Fine Structure
- ⑧ Bio Nano crystallography
- ⑨ High Energy Microscopy
- ⑩ NanoProbe



System Configuration of KLS

Linear Accelerator

Electron beam generation
& acceleration
(4 MeV → 200 MeV)

Booster Ring



Electron beam energy
acceleration
(200 MeV → 4 GeV)

Storage Ring

Electron beam storage &
photon beam generation



Beamline

Photon beam transport,
focusing, selection &
experiments



System Development

Photocathode-driven injector linac design for Korea-4GSR (TU1A004) By Dr. Chang-ki Min



Injector with Photocathode Electron Gun



70 MW Klystron

Electron Gun

Parameters	Multi-bunch	Single-bunch
Beam Energy	4 MeV	4 MeV
Charge	1 ~ 3 nC	0.01 ~ 1 nC
Pulse Length	128 ns (64 pulses)	≤ 20 ps
Repetition Rate	2 Hz	2 Hz

Linear Accelerator

Parameters	Multi-bunch	Single-bunch
Beam Energy	200 MeV	200 MeV
Frequency	2997.56 ± 0.1 MHz	2997.56 ± 0.1 MHz
Emittance (at 200 MeV)	≤ 10 nm	≤ 10 nm
Relative Energy Spread (rms)	$\leq 0.3\%$	$\leq 0.3\%$
Pulse-to-Pulse Energy Jitter (rms)	$\leq 0.2\%$	$\leq 0.2\%$
Bunch Charge (Charge Stability)	1 to 3 nC (5%)	0.01 to 1 nC (2%)
Pulse Duration	≈ 128 ns (64 bunches)	6–8 ps FWHM
Repetition Rate	2 Hz	2 Hz

Future Plan (Draft)

'24. Design Completion

'26. Start of Main Construction

'29. Project Completion

✓ Accelerator System & Beamlines

- '24. 04. Completion of Final Design
- '24. 10. Adjustment of Total Project Budget
- '24. H2 Manufacturing of Equipment
- '26. ~'28. Delivery and Test of Equipment
- ~'29. Installation of Equipment
- '29. ~ Commissioning

✓ Infrastructure

- '22. 09. Selection of Design Company & Start of Design
- '23. 09. Completion of Intermediate Design
- '24. 11. Completion of Final Design
- '26. 05. Groundbreaking
- '29. Completion of Facility Construction

✓ Site Development



- '24. H2 Site Preparation for Accelerator Bldg. Construction
- '26. 04. Land Provision Agreement
 - ※ Agreement Parties:
Chungcheongbuk-do & Cheongju City
<-> KSI


✓ Power Supply Infrastructure (Power Grid Connection)

- '24. H1 Detailed Design Service
- '25. 06. Start of Construction
- '27. Completion of Construction



RAON at Daejeon





Goal To build a heavy-ion accelerator complex **RAON** for rare isotope science research in Korea

Status Rare Isotope Science Project (RISP) : Dec. 2011 – Dec. 2022
RISP is changed to "IRIS" as of July 1, 2022. (From project to operation)
R&D for high-energy linac (SCL2) : Dec. 2022 – Dec. 2027




RAON Rare Isotope Accelerator Complex

Campus Area: 952,066 m²

- Accelerator System
- RI production System
- Conventional Utilities
- Experimental System



Brief History of RAON : RISP to IRIS



2011

2015

2019

2023


2026

- '10.02 Preliminary Design Study
- '11.02 Conceptual Design Study
- '11.11 IBS Established
- '11.12 Rare Isotope Science Project (RISP)
- '14.02 Purchasing the Land (RAON Site)
- '17.02 Civil Construction started

- '19.04 RISP moved on RAON site
- '19.09 Installation Started
- '20.09 QWR CM Installation
- '21.12 HWR CM Installation
- '22.07 Institute for Rare Isotope Science
- '22.08 SCL3 Cryoplat commissioning
- '22.12 1st Phase Completed


- '23.03 1st ISOL RIB Production
- '23.05 SCL3 Beam commissioning
- '23.12 1st Call for Proposals
- '24.03 1st PAC meeting
- '24.07 User Beam Experiments started
- '25.01 2nd Call for Proposals
- '25.05 2nd PAC meeting
- '25.09 3rd Call for Proposals
- '26.01 3rd PAC meeting

RAON Accelerators




Injector System

- **Two ECR-IS on high voltage platforms**
 - 14.5 GHz ECR ion source
 - 28 GHz superconducting ECR ion source
- **LEBT ($E = 10 \text{ keV/u}$)**
 - 10 keV/u, Dual bending magnet
 - Chopper & Electrostatic quads, Beam instrumentation
- **RFQ ($E = 500 \text{ keV/u}$)**
 - 81.25 MHz, Transmission Eff. $\sim 98\%$
 - CW RF Power 94 kW (SSPA: 150 kW)
- **MEBT ($E = 500 \text{ keV/u}$)**
 - Four RF bunchers (SSPA: 20, 15, $2 \times 4 \text{ kW}$)
 - Eleven quadrupole magnets, Beam instrumentation




- Installation completed and beam commissioning from October, 2020


Superconducting Linear Accelerator




Superconducting Linac 3 (Low-energy section)




Superconducting Linac 2 (High-energy section)



Layout of Cryogenic Distribution Systems



Superconducting linear accelerator (SCL3) in the tunnel



라온의 저에너지 가속구간은 올해 3월
 말까지 빔 시운전을 완료한다. 빔 인젝 시험의
 총괄책임자인 정연세 IBIS 중이온가속기연구소
 시스템통합부장은 "입막임이 크다"면서도
 과학자들이 독자롭게 "시험 가동이 순조롭게
 끝나기를 기원해달라"는 메시지를 전했다.

1st Cool-down of SCL3 in 2022.9-2023

2022

2023

• Sep. 7th – Oct. 26th
Cooldown under 4.5 K

• Nov. 24th – Jan. 11th
1st cooldown under 2 K

• Feb. 21st – 24th
2nd Cooldown under 2 K

• Apr. 21st
3rd Cooldown under 2 K

• Jun. 8th – 31st
Warmup

• Sep. 21th – Oct. 7th
Beam commissioning (6 QWR)


• Nov. 4th – Dec. 16th
Beam commissioning (22 QWR)

• Feb. 27th – Jun. 7th
Beam commissioning (SCL3)

◆ Cooling strategies

- Step 1 : Step Cool-down(20K~50K) controlled by Turbine 1 → “SCL3 CBx + HDS(TBX / CTL / EBx)+THS(HDS/CM)”
- Step 2 : QWR/HWR fast cool-down(150K ~ 50K / one by one)

TAO-induced icing




Cooldown from 300 K to 4.5 K




Cooldown from 4.5 K to 2.05 K

Cool-down (3rd) of SCL3 in 2025



SCL3 SI Beam Commissioning (2024~2026)




	2024	2025	2026
Particle	$^{40}\text{Ar}^{8+}$	$^{40}\text{Ar}^{8+}$	$^{22}\text{Ne}^{6+}$, $^{40}\text{Ar}^{8+}$ & $9+$
Current (MEBT, μA)	42.4	46	3, 46, 20
QWR Field(MV/m)	5.0	5.0	5.0
HWR-A Field (MV/m)	5.0	5.0	5.0
HWR-B Field (MV/m)	(< $\pm 1\%$, < $\pm 1^\circ$)	5.5	5.5
QWR (Unused cavities)	19 (3, 12, 21)	19 (6, 16, 18)	19 (6 , 16 , 18)*
HWRA (Unused cavities)	24 (6, 8)	21 (6, 17&18, 25&26)	22 (17&18 , 25&26)**
HWRB (Unused cavities)	71 (24, 28, 61)	72 (2, 37)	68
SCL3 energy (MeV/u)	16.4	~19.2	~24.5 MeV/u($^{22}\text{Ne}^{6+}$, $A/q=3.7$), ~21 MeV/u($^{40}\text{Ar}^{9+}$, $A/q=4.4$)
Transmission(SCL3)	91~93%	~91%	~93%

* Unable to tune cavity to resonance frequency(81.25 MHz) due to **tuner failure**

** 2 HWR CMs with the **upgraded couplers and tuners** are **under evaluation** at the SRF test facility.

SCL3 Beam Operation in 2026

Total beam delivery time = 226 hours
*Beam to Exp. during 4.20~7.10



- ❖ Total available beam time in 2026: ~ 1,000 hours planned
- ❖ Accelerator Beam Availability: ~98 % during regular experiments (KO-. ND-)
- No major downtime in key accelerator components (Injector, SCL3)
- Lower Beam Availability due to users requested beam stops
- ❖ Cryogenic system recovery took ~3 days after a brief power glitch (0.2s, June 8)
- ❖ Demonstrated $^{24}\text{Na}^{5+}$, $^{22}\text{Na}^{6+}$ (RI) beam acceleration/delivery based on the Ar, Ne (SI) beam commissioning

SCL2 R&D project (2022.12~2027.12)

- **Purpose:** Develop and validate key enabling technologies for SCL2 prior to mass production.
- **Scope:**
 - 1) Fabrication of prototype CM for both SSR1 and SSR2 of SCL2 (one unit each)
 - 2) Demonstration of Phase-1 prototype CM's performance
 - 3) SRF technology development and operation
 - 4) Project management and coordination



Cavity Type	Manufacturer	Vertical Test(VT)	Horizontal Test(HT)
$\beta=0.32$ SSR1	VitzroNextech	Ongoing	By 2027
$\beta=0.51$ SSR2	IHEP(China)	Old) under surface treatment New) kick-off fabrication	Old) by 2026 New) by 2027



◆ **(SSR1 Balloon-type)** Design and engineering are led by IRIS, while the manufacturing process development is carried out by a domestic company ('24.1, VITZRO Tech)

- Jacket material of SSR1 cavity has been changed from STS (prototype #1) to Titanium (prototype #2)
- $\beta = 0.29$ HWR considered as an alternative due to SSR1 fabrication complexity.

◆ **(SSR2 Cylinder-type)** Considering the high technical complexity, we maximally utilize the use of external resources (KAT & IHEP) from engineering design to manufacturing

Summary and Outlook

- ❖ **KOMAC** - Reliable 100 MeV proton linac operation; **200 MeV upgrade** under consideration
- ❖ **PAL-XFEL** - Stable 10.5 GeV XFEL operation; **HX2 and multi-FEL operation** in progress
- ❖ **KLS** - New 4 GeV light source under construction; **commissioning planned from 2029**
- ❖ **RAON** - SCL3 in user operation with high availability; **SCL2 technology R&D ongoing**

Korea continues to advance through reliable user operation, facility upgrades, new construction, and next-generation accelerator technologies.

Acknowledgment: Special thanks to KOMAC, PAL-XFEL, and KLS for providing materials for this presentation.