

The status of CiADS linac

— Design, Integration & Commissioning

Yuan He

on behalf of CiADS linac team

Institute of Modern Physics, Chinese Academy of Sciences

- **Introduction of CiADS**
- **Challenge and Design of Linac for CiADS**
- **Progress of the CiADS Linac**
- **Future Application Plan**

Fission Fuel
Scarcity


Spent/Waste
Fuel
Management

Nuclear
Safety

Proliferation
Risks

- Early 2026, WNA reported the aggressive plan of NP globally more than 1,446 GWe, means natural U 14 Mts, far more than the Global proven amount 8 Mt

10 kt natural U



1.5 kt fuel



1GWe
PWR

1.5 kt SF



radiation
~300k years



recyclable resources,
1.44 kt




0.06 kt used
FPs



- 1 MWe Reactor needs natural U ~10 kt during lifetime, Resource utilization Efficiency <1%
- High level radiation waste lifetime is more than 300k years, and has not final solution

Breeding and Transmutation

- $\text{U-238} \rightarrow \text{Pu-239}$ (fissile)
- $\text{Th-232} \rightarrow \text{U-233}$ (fissile)



- $\text{MAs} \rightarrow$ fission products (transmutation)



Breeding sufficient fissile nuclides and separating economically

$<1\% \rightarrow \sim 100\%$

■ ADS enables flexible transmutation and breeding



□ Reactivity control of subcritical fast reactors:

$$W_{\text{reactor}} = [I \times z_0] \times \varphi^* \times \left[\frac{QK_{\text{eff}}}{v(1 - K_{\text{eff}})} \right]$$


External source
neutron

External source
efficiency

External source
Magnification factor



High tolerance for fuel composition; allow to add SF, MAs, and DU in equilibrium cycles




- **Mixed Fuel “PUMA”:**
Pu+U+MA_s + a few FPs
 - High-temperature Dry Processing
 - Eco Regeneration (remove ~80% FPs)
- **Incineration:**
Acc + Sub-FR (ADS)
 - Inherently Safer (Sub-Critical)
 - Fast Breeding (1.3 ~ 2 times)
 - Transmutation (10 ~20 PWRs)

- Utilization rate of uranium resources : $\sim 0.6\% \rightarrow \sim 95\%$, **100**
- Radioactive waste lifetime : $\sim 400,000$ of years $\rightarrow \sim 400$ years, **1/1000**
- Radioactive effluent : $\sim 25\text{t} \rightarrow \sim 1\text{t}$ (1GWe/pile year) **1/25**
- Reactivity control : Critical operation $\rightarrow$ Subcritical operation


CiADS (China initiative Accelerator Driven System): the world's first MW-class research facility & fuel cycle capable of high-power coupling operation.

ADS thermal power = 10 MW:

- Accelerator beam power = 2.5 MW
- Pb-Bi spallation target power = 2.5 MW
- Subcritical Pb-Bi reactor power = 7.5 MW



T1: ADS Transmutation Research Terminal
T2: Advanced Target Technology Research Terminal
T3: Nuclear Functional Material Irradiation Terminal
T4: ADS Nuclear Database Terminal



Validation of spent fuel regeneration technology enabling 30% of U-utilization:

- Conduct breeding/transmutation experiments of **high-temp dry-processed fuel** in the ADS burner to verify **30% U-utilization cycle**

2026

2027

2028~2029

2030~2031

Accelerator Acceptance

- Accelerator 25kW
- Target >25kW
- Thermal test terminal

- 600 MeV accelerator trial run
- 250 kW target trial run
- Model spent fuel separation & fabrication
- First regenerated pellet fabricated

Spallation Target Acceptance

- Accelerator 250kW
- Target 250kW
- $k_{eff} \sim 0.4$
- Reactor 30kW

- ADANES burner commissioning
- Pilot fuel assembly insertion
- Industrial validation of high-temperature dry processing
- First regenerated fuel rod fabricated

ADS System Acceptance

- Accelerator 0.25~2.5MW
- Target 0.25~2.5MW
- $k_{eff} \sim 0.4-0.75$
- Reactor Power Ramping

- Fuel loading license obtained
- Burner operates at full power
- Metallic FP separation thermal test
- First regenerated fuel assembly

Fuel Cycle Validation


- Accelerator ~2.5MW
- Target ~2.5MW
- $k_{eff} \sim 0.75$
- Reactor ~7.5MW

- Regenerated fuel loading license obtained
- First loading of regenerated fuel
- Full-power breeding and transmutation testing
- Verified key technology integration for 100-MW-class ADANES facility

- Introduction of CiADS
- **Challenge and Design of linac for CiADS**
- Progress of the CiADS Linac
- Future Application Plan

Key Performance Specifications:


- ◆ **Accelerator Length:** ~300 m, Complex Cryogenic Distribution System
- ◆ **Beam Power:** > 3 MW (600 MeV, 5 mA), Beam Loss: < 1 W/m
- ◆ **Machine Protection:** < 20 μ s response



Energy/MeV	500~1000
Beam current/mA	5 ~10
Operation mode	Pulse & CW
Current stability	$\pm 2\%$ @100ms
Cavity number	151
CM number	32

Key Performance Specifications:

- ◆ **Accelerator Length:** ~300 m, Complex Cryogenic Distribution System
- ◆ **Beam Power:** > 3 MW (600 MeV, 5 mA), Beam Loss: < 1 W/m
- ◆ **Machine Protection:** < 20 μ s response



Beam Trip Duration	Industrial Scale Transmutation	Remarks
T<1sec	<25000	Target window lifetime
1sec<T<10sec	<2500	Fatigue failure of fuel cladding
10sec<T<5min	<2500	Fatigue failure of inner barrel and reactor vessel
T>5min	<50	System Availability

Critical physics challenges:

- ◆ **Ultra-low Beam Loss Control :** < 10^{-6}
- ◆ **Beam trip Availability:** > 85%

Concept of hardware design for an ADS-oriented linac

- **Modularization**
 - High-power component topology: parallel multi-module architecture, hot-swappable
- **Redundancy**
 - At least one spare module / pallet of redundancy; hot-swap supported with no functional interruption
 - Compensation capability via spare power margin
- **High power efficiency**
 - Balanced trade-off between power efficiency and redundancy
- **Edge intelligence**
 - Efficient monitoring, logging and fault troubleshooting for component status
- **Cloud brain**
 - AI-driven strategy leveraging full beam diagnostics feedback (position, profile, beam loss, etc.)
 - Automated commissioning and beam tuning

Beam loss control

- to make a high-quality beam at the warm front end
- to minimize beam loss at the superconducting section
- to avoid tiny unnecessary beam loss along the linac - Low temperature detector
- to detect sudden loss happens at any position of all the linac -Beam instrumentations

Fast beam recovery

- Hybrid fault-compensation for element fault-compensation
- Auto recovery scenario and technique in a few seconds
- Hot-swap technology based on modularization design of hardware


Operation stability

- Beam Control with Reinforcement Learning
- Virtual accelerator program development


CAFe to demonstrate 10-mA CW proton

- CAFe facility was constructed 2011-2021
- Demonstrated 10 mA, 200 kW CW beam in 2021, more than 100 hours operation higher than 100 kW, availability duration high than 93%.

in 2021
10mA, 200kW, CW



Ions	P
Frequency	162.5 MHz
Current	10 mA
E in RFQ	35 keV
E out RFQ	2.1 MeV
Energy	20MeV
Temp.	4.5 K




- **Supported by** “Strategic Priority Research Program” of the Chinese Academy of Sciences.

The status of CIADS linac, Daejeon, 16–21 August 2026

China Accelerator Facility for super-heavy Elements


➤ Research on the synthesis of the new elements 119 and 120



	Parameters	Units
Ions	Ca~Zn	-
A/q	3	-
Energy	4.0-6.5	MeV/u
Current	1~10	puA
Modes	CW	-

- 7000 hrs./yr since 2023
- Availability > 93%
- Produce 11 new nuclides, including the 115th Mc
- Reach 15 puA HI beam



Spectrometer for Heavy Atoms and
Nuclear Structure (SHANS2)









- **LEBT** : Transverse beam quality control- **Bend structure** + **beam scraping**
- **RFQ** : Longitudinal beam quality control- **Full particle optimization**
- **MEBT**: Beam halo control- **Full space scraping**
Phase space reconstructing

- **Low beam loss control**
 - ✓ **Lattice optimization** compact quasi-periodic structure and periodic lattice
 - ✓ **Beam matching** for mitigating halo formation and beam emittance growth
 - ✓ **Beam halo collimation** to reduce the probability of beam loss on SC elements


- **Beam uniformity by Multi order Sine wave scanning**
 - Collimation at A2T
 - Fourier harmonic superposition based on RF cavities





162.5MHz / 325MHz / 650MHz



AVAS - a PIC code Base on CPU and GPU, GPU is 1000 times faster than CPU



Ultra-large-scale simulation:
Accurately locate beam loss status, analyze fine beam structure and beam halo evolution, 50k, 5million, and 50million



Ultra-high-speed simulation:


increasement of three orders , 50-million scale can be completed within 2 minutes for the CiADS linac

parti-num	Time (s) (1 CPU Core)	Time (s) (56 CPU Core)	Time consumption(s) A100	
			1 A100	4 A100
10 ⁶	17486. 28	5242. 57	11. 55	—
10 ⁷	179255. 50	26021. 41	80. 50	36. 43
5*10 ⁷	896277. 50	119213. 64	367. 76	107. 78



The status of CIADS linac, Daejeon, 16–21 August 2026

Match compensation to avoid beam loss by adjusting the neighboring cavities and magnets of the failure cavity







Energy compensation by the reserved cavities in the high energy part




Twiss parameters matching



Energy compensation




Larger acceptance vs Local compensation




Hybrid fault compensation scheme : Balancing **Parameters Matching** and **Compensation Efficiency**


Design method based on Reinforcement Learning



● Quick response ability




Genetic Algorithm




Reinforcement Learning Algorithm

● Strong generalization ability




Compare with Traditional optimization algorithms:

- ① Less step better performance
- ② works in more situations




In the face of the **high-dimensional** and **nonlinear challenges** posed by failure compensation problems, **reinforcement learning algorithms** represent a more optimal choice.



PRAB 2023, Medium-Energy Orbit Correction


Demonstration of transferable RL orbit correction algorithms



SCPMA 2025, 超导段轨道校正SC Section Orbit Correction


Proposed nonlinear-dynamics-based accelerator controller design; achieved 42-dimensional full-beamline orbit correction.

Both approaches now routinely used in CAFE2 daily commissioning, significantly enhancing operation efficiency




NST 2025 (Editor-Recommended), CAFE2 Cavity Fault Detection, Accuracy: 96% (FPGA deployment pending)


Efficient beam tuning




Reliable operation



High-fidelity fast surrogate model




Driving full smart accelerator O&M from software to hardware



NIMA2021, CAFE2 EM Oscillation Fault ID


AI modeling of SC cavity mechanical modes
Deployed for CAFE2 operation, drastically reducing EM oscillation frequency (10→0.4/day)



IJMPA 2023, CAFE2 Phase-Space Surrogate Model

High-speed lattice optimization with real-time fault compensation

- Introduction of CiADS
- Challenge and Design of linac for CiADS
- **Progress of the CiADS linac**
- Future Application Plan



- ❑ Total 151 superconducting cavities with five cavity types for the CiADS linac
 - HWR010(9)/HWR019(24)/HWR040(60) & Elliptical062(30)/Elliptical082(28)
- ❑ The baseline is bulk niobium cavity
 - Prototype meets the requirement of operation at 2K
- ❑ Cu/Nb and Nb₃Sn/Nb Composite Cavity as an alternative choice for 4.2K operation
 - Thermal stability, Mechanical stability

HWR010 * 9

HWR019 * 24

HWR040 * 60

Ellip062 * 30






Ellip082 * 28

2025.08

2025.11

2026.04

2026.09



- 5 types of superconducting cavities, 151 units; a Universal Power Coupler Developed for 5 types of cavities

The status of CIADS linac, Daejeon, 16–21 August 2026



Four HPR systems



Two Strings assembly workstations

Quality Inspection upon Entry



Adopt strict quality inspection standards and prohibit risk components entering the cleanroom

项目看板


质检任务完成数

719

QC task

质检合格率

空值 合格 不合格




已完成检漏任务

279

Leak check tasks

检漏通过率

空值 是 否 空值



质检看板



Building an Electronic Task Management System

- The horizontal test of prototype cryomodule was completed, with mass production initiated concurrently.

2024.10

2025.09

2026.05

2026.09

- HWR-type cryomodules have been installed in the tunnel (H010*1, H019*4, H040*10)

- The integration and assembly of cryomodule has commenced.

- 32 Cryomodules in 5 families, 4 types were installed
- Elliptical 082 cryomodules will be presented in Sept.
- 6 assembly lines in parallel, 25 days for dirty assembly


- E062*10 have installed and E082*7 will be ready in Sept.
- All CMss will cooldown in Oct.
- Helium processing and plasma cleaning system will be online version.



System-level performance and hot-swapping verification of the SSPA.




(a) 650 MHz / 70 kW SSPA System (Front View)



(b) 650 MHz / 70 kW SSPA Output Power, Gain, and Efficiency



(c) Hot-Swapping of a Faulty PA Module During Operation



(d) Hot-Swapping and Fault-Isolation Test Results

High-power performance

- Maximum power reach 76.5 kW, exceeding the nominal 70 kW, with a gain plateau of approximately 75.5 dB.

High-efficiency operation

- The system achieved an efficiency of 62.5% at 70 kW, demonstrating efficient operation near the nominal power.

Hot-swapping capability

- A faulty PA module was removed and reinserted during operation, with the output power recovering to 99.94% of the initial 70 kW level.



CIADS HPRF Power System

Overall Integration Progress: 80%


The on-site installation and commissioning of the CIADS HPRF power system are steadily advancing.

The status of CIADS linac, Daejeon, 16–21 August 2026

➤Modulization of Power Supply

- ✓ All 74 cabinets have been installed in position, with both power and water supplies in place.
- Expected completion of off-line commissioning for all line power supplies by the end of August.

Section	Cabinet Count	Commissioning Status & Follow-up Plan
LEBT&MEBT	9	Real-load long-duration rated-current output test completed.
LBHL	5	Local off-line commissioning completed (short-circuit output current, main coil energy dumping). Awaiting superconducting conditions for integrated testing and real-load power-on testing.
MBHL	12	
HBHL	10	
LBEL	10	Complete local off-line commissioning.
MBEL	11	
HBET	13	Local off-line commissioning (short-circuit output current) expected to be completed by end of August.
A2D	4	



GIANT-General Intelligent Accelerator information Terminal

- ✓ LLRF
- ✓ BPM
- ✓ PS controller
- ✓ DCCT/ACCT
- ✓ Interlock/MPS/BPS
- ✓ CM controller
- ✓ AMP
- ✓ Temp

GIANT Generations:

- G1 is online for HIAF;
- G2 with WR on board is online for IP-SAFE;
- G3 with WR and safty ready for CiADS

function cards



AD/DA



IO



voltage



DIO



Temp



485/232



Mother board



ZU19EG



ZYNQ7045



ZYNQ7020

core



GIANT



- RF measurement
- IV conversion
- ARC detector
- isolation

Progress of the CiADS Linac – cryogenic

the first 18 kW cryoplant
made in China

first liquid helium successfully produced

cryogenic system (refrigerator, cryogenic
distribution system and supporting facilities)
fully installed; and is commissioning with
cryomodules

2025.05



2025.12

2026.06



2026.08

18kW@4.5K (4kW@2K) helium
refrigerator relocated and positioned


4K commissioning completed with
120-hour continuous operation




The status of CIADS linac, Daejeon, 16–21 August 2026



Ion Source beam commissioning



RFQ conditioning




SC section warm conditioning

162.5MHz / 325MHz / 650MHz

superconducting section







acc. facility

Reactor


Exp.
Hall

- Licensing:**
- Safety Design Criteria is on the first turn of Q&A.
 - The review of PSAR (priliminary safty analysis report) will start in months.

The status of CIADS linac, Daejeon, 16–21 August 2026

- Introduction of CiADS
- Challenge and Design of linac for CiADS
- Progress of the CiADS linac
- **Future Application Plan**

Terminals of HP proton beam



10 MWt Sub-critical
LBE fast reactor

First Proton Beam

- on target in 2027
- nuclear data in 2027
- uSR beam in 2028

Proton
600 MeV, 5 mA

High Power Proton

- 300 kW at uSR in 2029
- 3 MW on target in 2029
- 3 MW in reactor in 2030

Thank you for your attention!

HIAF

CiADS

