



Contribution ID: **2666** Contribution code: **WEPA166**

Type: **Poster Presentation**

## **RF preparation of QWR cavities for beam commissioning**

*Wednesday, 10 May 2023 16:30 (2 hours)*

QWR cavities are prepared for beam commissioning. RF conditioning is performed for each QWR cavity. The total heat load including static and dynamic heat loads are measured for each cavity. The helium pressure fluctuation is reduced by changing the flow rate, supply pressure, return pressure, liquid helium level in reservoir, cryogenic valve control, etc. The cavity pressure is monitored during RF preparation. The amplitude and phase of the QWR cavity are stably controlled for beam commissioning.

### **Funding Agency**

### **Footnotes**

### **I have read and accept the Privacy Policy Statement**

Yes

**Primary author:** KIM, Heetae (Institute for Basic Science)

**Co-authors:** GIL, Danhye (Institute for Basic Science); JANG, Hyojae (Institute for Basic Science); KIM, Juwan (Institute for Basic Science); SON, Ki Taek (Institute for Basic Science); LEE, Min Ki (Institute for Basic Science); JEON, Sungmin (Kyungpook National University); KI, Taekyung (Institute for Basic Science); JUNG, Yoochul (Institute for Basic Science); KIM, Youngkwon (Institute for Basic Science)

**Presenter:** KIM, Heetae (Institute for Basic Science)

**Session Classification:** Wednesday Poster Session

**Track Classification:** MC7: Accelerator Technology and Sustainability: MC7.T07: Superconducting RF